BRUHATH BANGALORE MAHANAGARA PALIKE, Dasarahalli Zone

Office of the Executive Engineer Project Division, Dasarahalli Zone, Bangalore-73

TENDER SCHDULE-B

Providing chainlink fencing to Alada ara Park 1 and 2 Ward No.12 Shettyhalli

Sl. No.	Qty	Description of Work	Unit
1	149.85	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width in Hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50m after breaking the clods complete as per specification.	cum
2	29.97	Providing and laying in position Plain Cement Concrete of Mix M10 with OPC @220kgs, using 20mm and down size graded granite metal coarse aggregates @0.84Cum and Fine aggregates @ 0.56 cum, machine mixed, concrete laid in layers not exceeding 15cm thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing, complete as per specification.	cum
3	79.20	Providing and constructing granite/trap/basalt Size Stone Masonry for Foundation in cement mortar 1:6 hammered dressed in courses not less than 20cm high, bond stones at two meter apart in each course including cost of materials, labour, curing complete as per specification.	cum
4	59.94	Providing and constructing granite/trap/basalt Size Stone Masonry in Basement in cement mortar 1:6 Edges of stones chistle dressed in courses not less than 15cm high, bond stones at two metre apart in each course including cost of materials, labour, curing complete as per specification.	cum
5	266.40	Providing raised and cut pointing to coursed stone masonry with CM 1:3, after taking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm

6	20.19	Providing and laying in position Plain Cement Concrete of Mix M20 with OPC @300kgs, using 20mm and down size graded granite metal coarse aggregates @0.64Cum and Fine aggregates @ 0.43 cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cm thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing, complete as per specification.	cum
7	399.60	Providing chain link fencing 50mm size of 8 Guage property Streched between rectangular poles and fixed with suitable bolts &nuts, the free ends shall be Welded to the pole abd black pipe at Top and bottom as required including cost of all materials, labour, laed and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint.	Sqm
8	244.20	Supplying and fixing M.S.Rectangular poles made out of 2equal angles of 65X65X6mm welded together and fixed in CC (1:2:4) WITH 2Nos 16mm dia M.S. hold fast rods each of length 25Cms. Including cost of all materials cutting. Bending Scaffolding wherever necessary. niely finishing the welded joints with all lead lifts and as per the directions of the Engineer- in- charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete).	M
9	40.00	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete as per Specifications. Of size 450x150x500mm	No
10	16.00	Provdining and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course snad for manufacture of blocks of approvede size, shape and colour with a minium comparessive strength of 281 kg per sqm over 50mm thick swand bed (average thickness) and compavating with plate of sand underneath to come up in between joints. final compaction of paver surface joints into its final level. including cost of all materials, labour, HOM of machaineries complete as per specificaions.	Sqm
11	68.40	Providing and applying enamel metal paint two coats (excluding priming coat)on previously painted steel or other metal surface brushing to give an even shade after cleaning oil, graese, dirt and other foreign matter.including cost of all materials, labour, complete as per Specifications.	Sqm

12	666.00	Providing and fix[illegible]k pipe of 38mm dia of heavy guage of 14 includ[illegible]ng the bends, cutting the pipe, and fixing the pipe in between the two verticle poles (M S rectangular poles) and spot welding the chain link with M S Block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-In-Charge of work etc., complete including two coats of approved quality paint over one coat of shop paint.	M
13	66.00	Providing and fixing with Back benches with back resting the set is inclusive of material cost transportaion charges including fixing the benches at the work spot (Approved rate)	No

~~DTS Approved~~

ಕಿರಿಯ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

Executive Engineer
Project Division, Dasarahalli Zone
B.B.M.P. Bangalore